



# City of Casa Grande

## Public Works Department

### INDUSTRIAL PRETREATMENT AERATION LAGOON BAFFLE REPLACEMENT PROJECT

#### Clarifications to Bid Documents:

##### *Regarding conflicts in project time / duration –*

A total of ninety (90) calendar days from the date of Notice to Proceed shall be provided for execution of this project.

##### *Completion of similar projects and references –*

Each bidder shall provide a list of at least three (3) similar projects, their dates, duration, cost, and contact information for owner's representative on the project. No form will be provided.

#### Response to Questions and Clarifications:

The following items/questions were discussed during the pre-bid meeting. The following answers/directions should be used by all interested contractors for bidding purposes:

- Alternate suppliers of the Hypalon material will be allowed provided they are “an approved equal” as determined by the City.
- All cables (upper and lower) are to be replaced with new.
- As it is uncertain how the lower cable is anchored, Contractor is to assume the need to install appropriate stainless steel anchors at the bottom of each column as needed. Anchors may be drilled and secured using an appropriate epoxy material.
- Ballast or sandbags at bottom are to be provided as recommended by the manufacturer and/or supplier. Intent of ballast is to aid in keeping curtains in place, not to provide a watertight seal.
- Each baffle-curtain is believed to be secured at each end by an existing stainless steel batten. The intent is to reuse these battens; however the Contractor shall be required to replace all fasteners and hardware.
- All hardware to be installed shall be stainless steel.
- Once a notice to proceed is issued, and the schedule provided by the Contractor is approved, the lagoon shall be scheduled to be drained in advance of the work.
  - It is intended that the work area shall be relatively dry prior to the Contractor mobilizing to the site, so no dewatering shall be required by the Contractor.
  - It is also intended that the work area within the lagoon be sufficiently clean prior to Contractor's work, thus no cleaning is considered to be required under this contract.
- Contractor shall be fully responsible for safety of their personnel and equipment on the site.
- No repairs to the existing liner are known to be required. Contractor shall be required to adequately protect the liner from the work, and shall be responsible for repairs at his sole expense should liner be damaged in the course of the work.
- Extension of anticipated project duration will be negotiated and provided should lead-time for procurement of materials be proven to be excessive.
- Curtains may be of any color
- Curtain sizes are to be as per those shown on the record drawings provided as part of the information package posted to prospective bidders.



**City of Casa Grande**

**Public Works Department**





**City of Casa Grande**

**Public Works Department**





**City of Casa Grande**

**Public Works Department**





# City of Casa Grande

---

## Public Works Department





**City of Casa Grande**  
**Public Works Department**

---

